

US EPA ARCHIVE DOCUMENT

**FINAL  
TOTAL MAXIMUM DAILY LOAD (TMDL)**

**For**

**Dissolved Oxygen**

**In**

**Jacks Branch  
(WBID 291)**

**May 2013**

**US EPA ARCHIVE DOCUMENT**





## TABLE OF CONTENTS

<b>1.0 INTRODUCTION</b> .....	<b>1</b>
<b>2.0 PROBLEM DEFINITION</b> .....	<b>1</b>
<b>3.0 WATERSHED DESCRIPTION</b> .....	<b>2</b>
3.1 CLIMATE .....	3
3.2 HYDROLOGIC CHARACTERISTICS .....	3
3.3 LAND USE .....	3
<b>4.0 WATER QUALITY STANDARDS/TMDL TARGETS</b> .....	<b>7</b>
4.1 DESIGNATED USES .....	7
4.2 WATER QUALITY CRITERIA .....	8
4.3 NUTRIENT CRITERIA .....	8
4.3.1 Narrative Nutrient Criteria.....	8
4.3.2 Inland Nutrient Criteria for streams.....	9
4.3.3 Inland Nutrient Criteria for estuaries with effective criteria.....	10
4.3.4 Inland Nutrient Criteria for lakes.....	10
4.3.5 Springs Nutrient Criteria.....	11
4.4 DISSOLVED OXYGEN CRITERIA.....	11
4.5 NATURAL CONDITIONS .....	11
4.6 BIOCHEMICAL OXYGEN DEMAND CRITERIA .....	12
<b>5.0 WATER QUALITY ASSESSMENT</b> .....	<b>12</b>
5.1 WATER QUALITY DATA .....	12
5.1.1 Dissolved Oxygen .....	12
5.1.2 Biochemical Oxygen Demand.....	13
5.1.3 Nutrients .....	13
5.1.3.1 Total Nitrogen .....	13
5.1.3.2 Total Phosphorus.....	13
5.1.3.3 Chlorophyll-a .....	14
<b>6.0 SOURCE AND LOAD ASSESSMENT</b> .....	<b>19</b>
6.1 POINT SOURCES .....	19
6.1.1 Wastewater/Industrial Permitted Facilities.....	19
6.1.2 Stormwater Permitted Facilities/MS4s.....	19
6.2 NONPOINT SOURCES .....	20
6.2.1 Urban Areas .....	21
6.2.2 Pastures .....	22
6.2.3 Clear cut/Sparse .....	22

6.2.4 Forests..... 22

6.2.5 Water and Wetlands..... 23

6.2.6 Quarries/Strip mines..... 23

**7.0 ANALYTICAL APPROACH..... 23**

7.1 MECHANISTIC MODEL ..... 23

7.2 SCENARIOS..... 26

7.2.1 Current Condition..... 26

7.2.2 Natural Condition..... 33

7.2.3 Reduction Scenario..... 40

**8.0 TMDL DETERMINATION..... 47**

8.1 CRITICAL CONDITIONS AND SEASONAL VARIATION ..... 49

8.2 MARGIN OF SAFETY ..... 49

8.3 WASTE LOAD ALLOCATIONS ..... 49

8.3.1 Wastewater/Industrial Permitted Facilities..... 50

8.3.2 Municipal Separate Storm Sewer System Permits ..... 50

8.4 LOAD ALLOCATIONS..... 51

**9.0 RECOMMENDATIONS/IMPLEMENTATION..... 51**

**10.0 REFERENCES..... 51**

US EPA ARCHIVE DOCUMENT

**LIST OF FIGURES**

Figure 2.1	Location of the impaired WBID in the Perdido River basin.....	2
Figure 3.1	Land use for WBID 291, Jacks Branch Creek, in the Perdido River basin.....	4
Figure 3.2	Aerial photo illustrating contributing subwatershed and impaired WBID boundaries.....	6
Figure 5.1	Water quality monitoring station locations for impaired WBID 291 in the Perdido River basin.....	14
Figure 5.2	Dissolved oxygen concentrations for WBID 291 .....	16
Figure 5.3	Biochemical oxygen demand concentrations for WBID 291.....	17
Figure 5.4	Total nitrogen concentrations for WBID 291 .....	17
Figure 5.5	Total phosphorus concentrations for WBID 291 .....	18
Figure 5.6	Corrected chlorophyll a concentrations for WBID 291 .....	18
Figure 7.1	Location of Jacks Branch Creek LSPC subwatersheds.....	24
Figure 7.2	Modeled vs. Observed Temperature (°C) at 21FLPNS 33010130 and 21FLBRA 291-A .....	27
Figure 7.3	Modeled vs. Observed Temperature (°C) at 21FLGW 34818 and 21FLGW 35227 .....	27
Figure 7.4	Modeled vs. Observed DO (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A .....	28
Figure 7.5	Modeled vs. Observed DO (mg/l) at 21FLGW 34818 and 21FLGW 35227.....	28
Figure 7.6	Modeled vs. Observed BOD <sub>5</sub> (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A .....	29
Figure 7.7	Modeled vs. Observed BOD <sub>5</sub> (mg/l) at 21FLGW 34818 and 21FLGW 35227.....	29
Figure 7.8	Modeled vs. Observed Total Nitrogen (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A.....	30
Figure 7.9	Modeled vs. Observed Total Nitrogen (mg/l) at 21FLGW 34818 and 21FLGW 35227.....	30
Figure 7.10	Modeled vs. Observed Total Phosphorus (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A.....	31
Figure 7.11	Modeled vs. Observed Total Phosphorus (mg/l) at 21FLGW 34818 and 21FLGW 35227.....	31
Figure 7.12	Modeled vs. Observed Chlorophyll a (ug/L) at 21FLPNS 33010130 and 21FLBRA 291-A .....	32
Figure 7.13	Modeled vs. Observed Chlorophyll a (ug/L) at 21FLGW 34818 and 21FLGW 35227.....	32
Figure 7.14	Modeled Natural Condition Temperature (°C) at 21FLPNS 33010130 and 21FLBRA 291-A.....	34
Figure 7.15	Modeled Natural Condition Temperature (°C) at 21FLGW 34818 and 21FLGW 35227.....	34
Figure 7.16	Modeled Natural Condition DO (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A.....	35

Figure 7.17	Modeled Natural Condition DO (mg/l) at 21FLGW 34818 and 21FLGW 35227.....	35
Figure 7.18	Modeled Natural Condition BOD <sub>5</sub> (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A .....	36
Figure 7.19	Modeled Natural Condition BOD <sub>5</sub> (mg/l) at 21FLGW 34818 and 21FLGW 35227.....	36
Figure 7.20	Modeled Natural Condition Total Nitrogen (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A.....	37
Figure 7.21	Modeled Natural Condition Total Nitrogen (mg/l) at 21FLGW 34818 and 21FLGW 35227 .....	37
Figure 7.22	Modeled Natural Condition Total Phosphorus (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A.....	38
Figure 7.23	Modeled Natural Condition Total Phosphorus (mg/l) at 21FLGW 34818 and 21FLGW 35227 .....	38
Figure 7.24	Modeled Natural Condition Chlorophyll a (ug/L) at 21FLPNS 33010130 and 21FLBRA 291-A.....	39
Figure 7.25	Modeled Natural Condition Chlorophyll a (ug/L) at 21FLGW 34818 and 21FLGW 35227.....	39
Figure 7.26	Temperature (°C) at 21FLPNS 33010130 and 21FLBRA 291-A in Nutrient Reduction Scenario .....	41
Figure 7.27	Temperature (°C) at 21FLGW 34818 and 21FLGW 35227 in Nutrient Reduction Scenario.....	41
Figure 7.28	DO (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A in Nutrient Reduction Scenario.....	42
Figure 7.29	DO (mg/l) at 21FLGW 34818 and 21FLGW 35227 in Nutrient Reduction Scenario .....	42
Figure 7.30	BOD <sub>5</sub> (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A in Nutrient Reduction Scenario.....	43
Figure 7.31	BOD <sub>5</sub> (mg/l) at 21FLGW 34818 and 21FLGW 35227 in Nutrient Reduction Scenario.....	43
Figure 7.32	Observed Total Nitrogen (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A in Nutrient Reduction Scenario .....	44
Figure 7.33	Total Nitrogen (mg/l) at 21FLGW 34818 and 21FLGW 35227 in Nutrient Reduction Scenario .....	44
Figure 7.34	Observed Total Phosphorus (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A in Nutrient Reduction Scenario .....	45
Figure 7.35	Total Phosphorus (mg/l) at 21FLGW 34818 and 21FLGW 35227 in Nutrient Reduction Scenario .....	45
Figure 7.36	Chlorophyll a (ug/L) at 21FLPNS 33010130 and 21FLBRA 291-A in Nutrient Reduction Scenario .....	46
Figure 7.37	Chlorophyll a (ug/L) at 21FLGW 34818 and 21FLGW 35227 in Nutrient Reduction Scenario .....	46
Figure 7.38	Dissolved Oxygen Concentration Cumulative Distribution Function .....	47

## LIST OF TABLES

Table 3.1	Land use distribution for WBID 291 in the Perdido River basin.....	5
Table 3.2	Land use distribution for contributing subwatersheds to WBID 291, Jacks Branch Creek.....	6
Table 4.1	Inland numeric nutrient criteria.....	7
Table 5.1	Water quality stations located in WBID 291, Jacks Branch Creek.....	14
Table 5.2	Water quality data for WBID 291, Jacks Branch Creek.....	15
Table 6.1	County estimates of Septic Tanks and Repair Permits. ....	22
Table 7.1	Current condition concentrations in the impaired WBID in the Perdido River basin.....	33
Table 7.2	Current condition loadings in the impaired WBID in the Perdido River basin. ....	33
Table 7.3	Natural condition concentrations in the impaired WBID in the Perdido River basin. ....	40
Table 7.4	Natural condition loadings in the impaired WBID in the Perdido River basin.....	40
Table 7.5	Reduction scenario concentrations in the impaired WBID in the Perdido River basin. ....	47
Table 7.6	Reduction scenario loadings in the impaired WBID in the Perdido River basin. ....	47
Table 8.1	TMDL Load Allocations for WBID 291 in the Jacks Branch Creek Basin.....	48

**SUMMARY SHEET for WBID 291**  
**Total Maximum Daily Load (TMDL)**

**2009 303(d) Listed Waterbodies for TMDLs addressed in this report:**

WBID	Segment Name	Class and Waterbody Type	Major River Basin	HUC	County	State
291	Jacks Branch	Class III Freshwater	Perdido Bay	3140106	Escambia	Florida

**TMDL Endpoints/Targets:**

Dissolved Oxygen

**TMDL Technical Approach:**

The TMDL allocations were determined by analyzing the effects of TN, TP and BOD concentrations on DO concentrations in the waterbody. A watershed model was used to predict delivery of pollutant loads to the waterbody and to evaluate the in-stream impacts of the pollutant loads.

**TMDL Waste Load and Load Allocation**

Constituent	Current Condition		TMDL Condition		Percent Reduction	
	WLA (kg/yr)	LA (kg/yr)	WLA (kg/yr)	LA (kg/yr)	LA	MS4
Total Nitrogen	NA	25,000	NA	14,090	44%	44%
Total Phosphorus	NA	488	NA	285	42%	42%
Biochemical Oxygen Demand	NA	69,408	NA	49,005	29%	29%

**Endangered Species Present (Yes or Blank):** Yes

**USEPA Lead TMDL (USEPA or Blank):** USEPA

**TMDL Considers Point Source, Non-point Source, or Both:** Non-point

**Major NPDES Discharges to surface waters addressed in USEPA TMDL:**

Permit ID	Permittee(s)	County	Permit Type
FLS000019	Escambia County, FDOT (District III)	Escambia	Phase I C MS4

US EPA ARCHIVE DOCUMENT

## 1.0 INTRODUCTION

Section 303(d) of the Clean Water Act requires each state to list those waters within its boundaries for which technology based effluent limitations are not stringent enough to protect any water quality standard applicable to such waters. Listed waters are prioritized with respect to designated use classifications and the severity of pollution. In accordance with this prioritization, states are required to develop Total Maximum Daily Loads (TMDLs) for those water bodies that are not meeting water quality standards. The TMDL process establishes the allowable loadings of pollutants or other quantifiable parameters for a waterbody based on the relationship between pollution sources and in-stream water quality conditions, so that states can establish water quality based controls to reduce pollution from both point and nonpoint sources and restore and maintain the quality of their water resources (USEPA 1991).

The Florida Department of Environmental Protection (FDEP) developed a statewide, watershed-based approach to water resource management. Under the watershed management approach, water resources are managed on the basis of natural boundaries, such as river basins, rather than political boundaries. The watershed management approach is the framework FDEP uses for implementing TMDLs. The state's 52 basins are divided into five groups and water quality is assessed in each group on a rotating five-year cycle. FDEP also established five water management districts (WMD) responsible for managing ground and surface water supplies in the counties encompassing the districts.

For the purpose of planning and management, the WMD divided the districts into planning units defined as either an individual primary tributary basin or a group of adjacent primary tributary basins with similar characteristics. These planning units contain smaller, hydrological based units called drainage basins, which are further divided by FDEP into "water segments". A water segment usually contains only one unique waterbody type (stream, lake, canal, etc.) and is about 5 square miles. Unique numbers or waterbody identification (WBID) numbers are assigned to each water segment. Located within the Perdido River Planning Unit, WBID 291 is a Group 5 waterbody managed by the Northwest Florida Water Management District (NFWFMD). WBID 291 is impaired for dissolved oxygen (DO).

## 2.0 PROBLEM DEFINITION

To determine the status of surface water quality in Florida, three categories of data – chemistry data, biological data, and fish consumption advisories – were evaluated to determine potential impairments. The level of impairment is defined in the Identification of Impaired Surface Waters Rule (IWR), Section 62-303 of the Florida Administrative Code (FAC). The IWR is FDEP's methodology for determining whether waters should be included on the state's planning list and verified list. Potential impairments are determined by assessing whether a waterbody meets the criteria for inclusion on the planning list. Once a waterbody is on the planning list, additional data and information will be collected and examined to determine if the water should be included on the verified list.

The TMDL addressed in this document is being established pursuant to commitments made by the United States Environmental Protection Agency (USEPA) in the 1998 Consent Decree in the Florida TMDL lawsuit (Florida Wildlife Federation, et al. v. Carol Browner, et al., Civil Action No. 4: 98CV356-WS, 1998). That Consent Decree established a schedule for TMDL development for waters listed on Florida's USEPA approved 1998 section 303(d) list. The 2009 section 303(d) list identified numerous WBIDs in the Perdido Bay Basin as not meeting WQS. After assessing all readily available water quality data, USEPA is responsible for developing a TMDL for WBID 291, depicted in Figure 2.1.




Figure 2.1 Location of the impaired WBID in the Perdido River basin.

### 3.0 WATERSHED DESCRIPTION

The Perdido River watershed is located along the Gulf Coast, with the river forming the boundary between Florida and Alabama. Its headwaters originate in Escambia County, Alabama which then flow south and form the boundary between Escambia County, Florida and Baldwin County, Alabama. While a majority of the basin is located within Alabama (815 square miles), approximately 33 percent lies within Florida (400 square miles) (FDEP 2006). The river discharges into Perdido Bay, which is connected with Pensacola Bay to the west through the Gulf Intracoastal Waterway, and exits to the Gulf of Mexico through Perdido Pass (FDEP).

Contributing tributaries found within Florida include Bushy Creek, Boggy Creek, McDavid Creek, and Jacks Branch (FDEP). The Perdido River is a sand-bottom river in the headwaters that progresses into a blackwater stream as it nears the Bay (FDEP). Additionally, several tributaries and portions of the Perdido River have been designated as Outstanding Florida Waters (FDEP 2006). Portions of the watershed reside in the Perdido River Management Area, which serves as a wetland mitigation area (NFWFMD 2012).

### **3.1 Climate**

The Perdido River watershed experiences a subtropical climate with hot, humid summers and mild, short winters. Temperatures in the summer can reach as high as the mid-to upper-90s (°F), and the low-40s (°F) in the winter (NOAA 2004). An average of 65 inches of rain every year is received in the Panhandle, of which a greater percentage falls during the wet season (May to October), coinciding with hurricane season (NFWFMD 2004). Drought conditions do occur at times, generally in the late spring or early fall (NOAA 2004).

### **3.2 Hydrologic characteristics**

Jacks Branch is a tributary of Perdido River and is part of the Perdido River Planning Unit. The headwaters of Jacks Branch originate in a large farming community known as Northgate Farms. The watershed has many unpaved roads, which support the relatively large farming and silviculture communities in the area (FDEP). Additionally, within the watershed is a Resources Conservation and Recovery Act (RCRA) site which had soil, groundwater, and surface water contamination, but the site has since been remediated (FDEP).

### **3.3 Land Use**

A majority of the land use within WBID 291 consists of combined forest, which accounts for 37 percent of the total land use (Figure 3.1 and Table 3.2). Pastures and row crops account for an additional 32 percent of total land use and are mainly located in the headwaters and upper reaches of Jacks Branch. Forested and non-forested wetlands are located primarily along the riparian corridors of Jacks Branch, and account for 17 percent of the total land use. There is limited development in WBID 291, most of which consists of transportation corridors or suburban areas outside the City of Gonzalez Park. Developed land accounts for 7 percent of the total land use in WBID 291. The remaining land use is attributed to small clear cut/sparse areas (6 percent), open water (1 percent) and utility swaths (1 percent).

The actual drainage area for Jacks Branch is approximately 74 percent larger than the WBID boundary (Figure 3.2). The United States Geological Survey National Hydrography Dataset was used to delineate the drainage area. Although the contributing area has increased, the land use composition is similar. Combined forest land uses account for the greatest land use classifications, comprising 35 percent of the total land use. Pastures account for 16 percent of the total land use, followed by row crops at 15 percent. Forested and non-forested wetlands account for 14 percent, while open water continues to be less than one percent of the total contributed drainage area. Developed land use from the actual drainage area increased by over 150 percent, accounting for 10 percent of the total contributed land use. Quarries and strip mines

continued to contribute less than one percent of total land use, along with utility swaths and golf courses. Clear cut/sparse land uses contribute 9 percent towards the total contributed land use.




Figure 3.1 Land use for WBID 291, Jacks Branch Creek, in the Perdido River basin.

Table 3.1 Land use distribution for WBID 291 in the Perdido River basin.

Land Use Classification	WBID 291	
	Acres	%
Evergreen Forest	2,549	29%
Deciduous Forest	29	0%
Mixed Forest	722	8%
Forested Wetland	1,316	15%
Non-Forested Wetland (Freshwater)	143	2%
Open Water	46	1%
Pasture	1,487	17%
Row Crop	1,284	15%
Clear cut Sparse	545	6%
Quarries Strip mines	43	0%
Utility Swaths	44	1%
Developed, Open Space	99	1%
Developed, Low intensity	0	0%
Developed, Medium intensity	288	3%
Developed, High intensity	210	2%
Beaches/Dunes/Mud	0	0%
Golf Courses	0	0%
<b>Totals</b>	<b>8,804</b>	<b>100%</b>




Figure 3.2 Aerial photo illustrating contributing subwatershed and impaired WBID boundaries.

Table 3.2 Land use distribution for contributing subwatersheds to WBID 291, Jacks Branch Creek.

Land Use Classification	Contributing subwatersheds	
	Acres	%
Evergreen Forest	3,785	25%
Deciduous Forest	217	1%
Mixed Forest	1,402	9%
Forested Wetland	1,777	12%
Non-Forested Wetland (Freshwater)	288	2%
Open Water	75	0%
Pasture	2,462	16%

Land Use Classification	Contributing subwatersheds	
	Acres	%
Row Crop	2,255	15%
Clear cut Sparse	1,353	9%
Quarries Strip mines	52	0%
Utility Swaths	74	0%
Developed, Open Space	183	1%
Developed, Low intensity	0	0%
Developed, Medium intensity	708	5%
Developed, High intensity	651	4%
Beaches/Dunes/Mud	0	0%
Golf Courses	25	0%
<b>Totals</b>	<b>15,282</b>	<b>100%</b>

## 4.0 WATER QUALITY STANDARDS/TMDL TARGETS

The TMDL reduction scenarios were done to achieve Florida's dissolved oxygen concentration of 5 mg/L and ensure balanced flora and fauna within these WBIDs or establish the TMDL to be consistent with a natural condition if the dissolved oxygen standard cannot be achieved.

### 4.1 Designated Uses

Florida has classified its waters based on the designated uses those waters are expected to support. Waters classified as Class I waters are designated for Potable Water Supply; Class II waters are designated for Shellfish Propagation or Harvesting, and Class III waters are designated for Recreation, Propagation and Maintenance of a Healthy, Well-Balanced Population of Fish and Wildlife. Designated use classifications are described in Florida's water quality standards at section 62-302.400, F.A.C.

The waterbody addressed in this report is a Class III water. WBID 291 is a Class III Freshwater.

## **4.2 Water quality criteria**

Water quality criteria for protection of all classes of waters are established in Section 62-302.530, F.A.C. Individual criteria should be considered in conjunction with other provisions in water quality standards, including Section 62-302.500 F.A.C., which established minimum criteria that apply to all waters unless alternative criteria are specified. Section 62-302.530, F.A.C. Several of the WBIDs addressed in this report were listed due to elevated concentrations of chlorophyll *a*. While FDEP does not have a streams water quality standard specifically for chlorophyll *a*, elevated levels of chlorophyll *a* are frequently associated with nonattainment of the narrative nutrient standard, which is described below.

## **4.3 Nutrient Criteria**

In 1979, FDEP adopted a narrative criterion for nutrients. FDEP recently adopted numeric nutrient criteria for many Class III waters in the state, including streams, lakes, springs, and estuaries, which numerically interprets part of the state narrative criterion for nutrients. On November 30, 2012, EPA approved those criteria as consistent with the requirements of the CWA. Estuary specific criteria for a number of estuaries, as set out in 62-302.532(1), are effective for state law purposes. The remainder of the state criteria, however, are not yet effective for state law purposes.

In December 2010, EPA promulgated numeric nutrient criteria for Class I/III inland waters in Florida, including lakes and streams. On February 18, 2012, the federally promulgated criteria for lakes and springs were upheld by the U.S. District Court for the Northern District of Florida. Those criteria became effective on January 7, 2013. The Court invalidated the streams criteria and remanded those criteria back to EPA. EPA repropose the streams criteria on November 30, 2012.

Therefore, for lakes and springs in Florida, the applicable nutrient water quality criteria for CWA purposes are the federally promulgated criteria. For those estuaries identified in 62-302.532(1), the applicable nutrient water quality criteria for CWA purposes are FDEP's estuary criteria. For streams and the remaining estuaries in Florida, the applicable nutrient water quality standard for CWA purposes remains Florida's narrative nutrient criterion.

### **4.3.1 Narrative Nutrient Criteria**

Florida's narrative nutrient criteria for Class I, II, and III waters provide:

The discharge of nutrients shall continue to be limited as needed to prevent violations of other standards contained in this chapter. Man induced nutrient enrichment (total nitrogen and total phosphorus) shall be considered degradation in relation to the provisions of Sections 62-302.300, 62-302.700, and 62-4.242. Section 62-302.530(47)(a), F.A.C.

In no case shall nutrient concentrations of a body of water be altered so as to cause an imbalance in natural populations of aquatic flora or fauna. Section 62-302.530(47)(b), F.A.C.

Chlorophyll and DO levels are often used to indicate whether nutrients are present in excessive amounts. The target for this TMDL is based on levels of nutrients necessary to prevent violations of Florida's DO criterion, set out below.

#### 4.3.2 Inland Nutrient Criteria for streams

Florida's recently adopted numeric nutrient criteria interprets the narrative water quality criterion for nutrients in paragraph 62-302.530(48)(b), F.A.C. See section 62-302.531(2). While not yet effective as water quality criteria, the FDEP's numeric nutrient criteria represent the state's most recent interpretation of the second part of Florida's narrative criteria, set out at paragraph 62-302.530(47)(b), F.A.C. See section 62-302.531(2). Unless otherwise stated, where the EPA refers to the state nutrient rule in this TMDL, that rule is referenced as the state's interpretation of the narrative criterion. In addition, the first part of the narrative criteria, at paragraph 62-302.530(47)(a), F.A.C., also remains applicable to all Class I, II and III waters in Florida.

Florida's rule applies to stream. For streams that do not have a site specific criteria, Florida's rule provides for biological information to be considered together with nutrient thresholds to determine whether a waterbody is attaining 62-302.531(2)(c), F.A.C. The rule provides that the nutrient criteria are attained in a stream segment where information on chlorophyll a levels, algal mats or blooms, nuisance macrophyte growth, and changes in algal species composition indicates there are no imbalances in flora and either the average score of at least two temporally independent SCIs performed at representative locations and times is 40 or higher, with neither of the two most recent SCI scores less than 35, or the nutrient thresholds set forth in Table 1 below are achieved. See section 62-302.531(2)(c).

Florida's rule provides that numeric nutrient criteria are expressed as a geometric mean, and concentrations are not to be exceeded more than once in any three calendar year period. Section 62-302.200 (25)(e), F.A.C.

Table 1 Inland numeric nutrient criteria

Nutrient Watershed Region	Total Phosphorus Nutrient Threshold	Total Nitrogen Nutrient Threshold
Panhandle West	0.06 mg/L	0.67 mg/L
Panhandle East	0.18 mg/L	1.03 mg/L
North Central	0.30 mg/L	1.87 mg/L
Peninsular	0.12 mg/L	1.54 mg/L

West Central	0.49 mg/L	1.65 mg/L
South Florida	No numeric nutrient threshold. The narrative criterion in paragraph 62-302.530(47)(b), F.A.C., applies.	No numeric nutrient threshold. The narrative criterion in paragraph 62-302.530(47)(b), F.A.C., applies.

#### 4.3.3 Inland Nutrient Criteria for estuaries with effective criteria

Numeric criteria for estuaries are expressed as either concentration-based estuary interpretations that are open water, area-wide averages or as load per million cubic meters of freshwater inflow that are the total load of that nutrient to the estuary divided by the total volume of freshwater inflow to that estuary. The criteria, set out at 62-302.532(1).

#### 4.3.4 Inland Nutrient Criteria for lakes

Federal water quality criteria for lakes set out at 40 CFR 131.43(c)(1). The criteria are expressed as concentrations of chlorophyll *a*, total phosphorus, and total nitrogen as follows:

Lake Color and Alkalinity	Chl- <i>a</i> (mg/L)*	TN (mg/L)	TP (mg/L)
Colored Lakes (Long-term Color > 40 Platinum Cobalt Units (PCU))	0.020	1.27 [1.27-2.23]	0.05 [0.05-0.16]
Clear Lakes, High Alkalinity (Long-term Color ≤ 40 PCU and Alkalinity > 20 mg/L CaCO <sub>3</sub> )	0.020	1.05 [1.05-1.91]	0.03 [0.03-0.09]
Clear Lakes, Low Alkalinity (Long-term Color ≤ 40 PCU and Alkalinity ≤ 20 mg/L CaCO <sub>3</sub> )	0.006	0.51 [0.51-0.93]	0.01 [0.01-0.03]

\* For a given waterbody, the annual geometric mean of chlorophyll *a*, TN or TP concentrations shall not exceed the applicable criterion concentration more than once in a three-year period.

#### 4.3.5 Springs Nutrient Criteria

The numeric criteria for spring is 0.35 mg/L of nitrate-nitrite as an annual geometric mean, not to be exceeded more than once in any three year period.

#### 4.4 Dissolved Oxygen Criteria

Numeric criteria for DO are expressed in terms of minimum and daily average concentrations. While FDEP has adopted revised DO criteria for freshwaters, these revisions have not yet been to EPA for review. Therefore, the applicable criterion for Clean Water Act purposes remains subsection 62-302.530(30), F.A.C.

**For Class I and Class III freshwaters**, subsection 62-302.530(30) provides as follows:

Shall not be less than 5.0 mg/L. Normal daily and seasonal fluctuations above these levels shall be maintained. [FAC 62-302.530 (30)]

**For Class III marine waters**, subsection 62-302.530(30) provides as follows:

Shall not average less than 5.0 mg/L in a 24-hour period and shall never be less than 4.0 mg/L. Normal daily and seasonal fluctuations above these levels shall be maintained. [FAC 62-302.530 (30)]

#### 4.5 Natural Conditions

In addition to the standards for nutrients, DO and BOD described above, Florida's standards include provisions that address waterbodies which do not meet the standards due to natural background conditions.

Florida's water quality standards provide a definition of natural background:

“Natural Background” shall mean the condition of waters in the absence of man-induced alterations based on the best scientific information available to the Department. The establishment of natural background for an altered waterbody may be based upon a similar unaltered waterbody or on historical pre-alteration data. 62-302.200(15), FAC.

Florida's water quality standards also provide that:

Pollution which causes or contributes to new violations of water quality standards or to continuation of existing violations is harmful to the waters of this State and shall not be allowed. Waters having water quality below the criteria established for them shall be protected and enhanced. However, the Department shall not strive to abate natural conditions. 62-302.300(15), FAC.

#### **4.6 Biochemical Oxygen Demand Criteria**

Biochemical Oxygen Demand (BOD) shall not be increased to exceed values which would cause dissolved oxygen to be depressed below the limit established for each class and, in no case, shall it be great enough to produce nuisance conditions. [FAC 62-302.530 (11)]

The waterbody addressed in this report is a Class III water having a designated use of Recreation, Propagation and Maintenance of a Healthy, Well-Balanced Population of Fish and Wildlife. Designated use classifications are described in Florida's water quality standards in Section 62-302.400, FAC. Water quality criteria for protection of all classes of waters are established in Section 62-302.530, FAC. Individual criteria should be considered in conjunction with other provisions in water quality standards, including Section 62-302.500 FAC, which established minimum criteria that apply to all waters unless alternative criteria are specified Section 62-302.530, FAC. In addition, unless otherwise stated, all criteria express the maximum not to be exceeded at any time. The specific criteria addressed in this TMDL document are provided in the following sections.

### **5.0 WATER QUALITY ASSESSMENT**

The WBID addressed in this report was listed as not attaining its designated use on Florida's 2009 303(d) list for dissolved oxygen and nutrients. To determine impairment, an assessment of available data was conducted. The source for current ambient monitoring data was the Impaired Waters Rule (IWR) data Run 44, using data ranging January 1, 2002 to December 31, 2010. The IWR database contains data from various sources within the state of Florida, including the WMDs and counties.

#### **5.1 Water Quality Data**

A complete list of water quality monitoring stations in WBID 291 is located in Table 5.1, and an analysis of water quality data is documented in Table 5.2. Figure 5.1 shows the locations of the water quality monitoring stations within the WBID. Water quality data for the WBID can be found below in Figure 5.2 through Figure 5.6, with the data from all water quality stations compiled in each figure.

##### **5.1.1 Dissolved Oxygen**

There are several factors that affect the concentration of DO in a waterbody, and natural DO levels are a function of water temperature, water depth and velocity, salinity and relative contributions from groundwater. Oxygen can be introduced by wind, diffusion, photosynthesis, and additions of higher DO water (e.g. from tributaries). DO concentrations can be lowered by processes that use up oxygen from the water, such as respiration and decomposition, and can be lowered through additions of water with lower DO (e.g. swamp or groundwater). Decomposition of organic matter, such as dead plants and animals, also consume DO. The dissolved oxygen minimum concentration was 0.61 mg/L, and the maximum concentration was 10.83 mg/L. The mean concentration was 5.87 mg/L.

### 5.1.2 Biochemical Oxygen Demand

Biochemical oxygen demand is a measure of the amount of oxygen used by bacteria as they stabilize organic matter. The process can be accelerated when there is an overabundance of nutrients, increasing the aerobic bacterial activity in a waterbody. In turn, the levels of DO can become depleted, eliminating oxygen essential for biotic survival, and potentially causing extensive fish kills. Additionally, BOD is used as an indicator to determine the presence and magnitude of organic pollution from sources such as septic tank leakage, fertilizer runoff, and wastewater effluent. The mean BOD concentration for WBID 291 was 1.33 mg/L. The maximum BOD concentration was 4.50 mg/L and the minimum concentration was 0.20 mg/L.

### 5.1.3 Nutrients

Excessive nutrients in a waterbody can lead to overgrowth of algae and other aquatic plants such as phytoplankton, periphyton and macrophytes. This process can deplete oxygen in the water, adversely affecting aquatic life and potentially restricting recreational uses such as fishing and boating. For the nutrient assessment the monitoring data for total nitrogen, total phosphorus and chlorophyll a are presented. Narrative nutrient criteria are used as the standards for estuarine water bodies, while numeric standards have been developed for freshwater water bodies. The current standards for nutrients are narrative criteria. The purpose of the nutrient assessment is to present the range, variability and average conditions for the WBID.

#### 5.1.3.1 Total Nitrogen

Total nitrogen (TN) is comprised of nitrate (NO<sub>3</sub>), nitrite (NO<sub>2</sub>), organic nitrogen and ammonia nitrogen (NH<sub>4</sub>). Though nitrogen is a necessary nutrient required for the growth of most plants and animals, not all forms are readily used or metabolized. Increased levels of organic nitrogen can occur from the decomposition of aquatic life or from sewage, while inorganic forms are generally from erosion and fertilizers. Nitrates are components of industrial fertilizers, yet can also be naturally present in soil, and are converted to nitrite by microorganisms in the environment. Surface runoff from agricultural lands can increase the natural presence of nitrates in the environment and can lead to eutrophication. Usually, the eutrophication process is observed as a change in the structure of the algal community and includes severe algal blooms that may cover large areas for extended periods. Large algal blooms are generally followed by depletion in DO concentrations as a result of algal decomposition. The total nitrogen minimum concentration was 0.08 mg/L, and the maximum concentration was 1.22 mg/L. The mean total nitrogen concentration in WBID 291 was 0.51 mg/L.

#### 5.1.3.2 Total Phosphorus

In natural waters, total phosphorus exists in either soluble or particulate forms. Dissolved phosphorus includes inorganic and organic forms, while particulate phosphorus is made up of living and dead plankton, and adsorbed, amorphous, and precipitated forms. Inorganic forms of phosphorus include orthophosphate and polyphosphates, though polyphosphates are unstable and convert to orthophosphate over time. Orthophosphate is both stable and reactive, making it the form most used by plants. Excessive phosphorus can lead to overgrowth of algae and aquatic plants, the decomposition of which depletes oxygen in the water.

The total phosphorus minimum concentration was 0.005 mg/L, and the maximum concentration was 0.082 mg/L. The mean total phosphorus concentration in WBID 291 was 0.02 mg/L.

**5.1.3.3 Chlorophyll-a**

Chlorophyll is the green pigment in plants that allows them to create energy from light. In a water sample, chlorophyll is indicative of the presence of algae, and chlorophyll-a is a measure of the active portion of total chlorophyll. Corrected chlorophyll refers to chlorophyll-a measurements that are corrected for the presence of pheophytin, a natural degradation product of chlorophyll that can interfere with analysis because it has an absorption peak in the same spectral region. It is used as a proxy indicator of water quality because of its predictable response to nutrient availability. Increases in nutrients can potentially lead to blooms in phytoplankton biomass, affecting water quality and ecosystem health. The corrected chlorophyll a maximum concentration was 18.70 µg/L, and the mean concentration was 3.75 µg/L.




Figure 5.1 Water quality monitoring station locations for impaired WBID 291 in the Perdido River basin.

Table 5.1 Water quality stations located in WBID 291, Jacks Branch Creek

WBID	Station Number
------	----------------

US EPA ARCHIVE DOCUMENT

<b>291</b>	21FLBRA 291-A
	21FLBRA 291-B
	21FLBRA 291-C
	21FLGW 34818
	21FLGW 35227
	21FLPNS 33010130
	21FLPNS 33010131
	21FLPNS 33010132

Table 5.2 Water quality data for WBID 291, Jacks Branch Creek

Parameter	Stats	WBID 291
BOD, 5 Day 20°C (mg/L)	# of obs	32
	min	0.2
	max	4.5
	mean	1.33
	Geomean	1.08
DO, Analysis by Probe (mg/L)	# of obs	36
	min	0.61
	max	10.83
	mean	5.87
	Geomean	4.99
Nitrogen, Total (mg/L as N)	# of obs	29
	min	0.08
	max	1.22
	mean	0.51
	Geomean	0.41
Phosphorus, Total (mg/L)	# of obs	29

Parameter	Stats	WBID 291
	min	0.005
	max	0.082
	mean	0.02
	Geomean	0.02
Chlorophyll-A-corrected (µg/L)	# of obs	36
	min	1
	max	18.7
	mean	3.75
	Geomean	2.41




Figure 5.2 Dissolved oxygen concentrations for WBID 291




Figure 5.3 Biochemical oxygen demand concentrations for WBID 291




Figure 5.4 Total nitrogen concentrations for WBID 291

US EPA ARCHIVE DOCUMENT




Figure 5.5 Total phosphorus concentrations for WBID 291




Figure 5.6 Corrected chlorophyll a concentrations for WBID 291

US EPA ARCHIVE DOCUMENT

## 6.0 SOURCE AND LOAD ASSESSMENT

An important part of the TMDL analysis is the identification of source categories, source subcategories, or individual sources of pollutants in the watershed and the amount of loading contributed by each of these sources. Sources are broadly classified as either point or nonpoint sources. Nutrients can enter surface waters from both point and nonpoint sources.

### 6.1 Point Sources

A point source is defined as a discernable, confined, and discrete conveyance from which pollutants are or may be discharged to surface waters. Point source discharges of industrial wastewater and treated sanitary wastewater must be authorized by National Pollutant Discharge Elimination System (NPDES) permits. NPDES permitted discharges include continuous discharges such as wastewater treatment facilities as well as some stormwater driven sources such as municipal separate stormwater sewer systems (MS4s), certain industrial facilities, and construction sites over one acre.

#### 6.1.1 Wastewater/Industrial Permitted Facilities

A TMDL wasteload allocation (WLA) is given to wastewater and industrial NPDES permitted facilities discharging to surface waters within an impaired watershed. There are no NPDES-permitted facilities in WBID 291.

#### 6.1.2 Stormwater Permitted Facilities/MS4s

MS4s are point sources also regulated by the NPDES program. According to 40 CFR 122.26(b)(8), an MS4 is “a conveyance or system of conveyances (including roads with drainage systems, municipal streets, catch basins, curbs, gutters, ditches, man-made channels, or storm drains):

- (i) Owned or operated by a State, city, town, borough, county, parish, district, association, or other public body (created by or pursuant to State law)...including special districts under State law such as a sewer district, flood control district or drainage district, or similar entity, or an Indian tribe or an authorized Indian tribal organization, or a designated and approved management agency under section 208 of the Clean Water Act that discharges into waters of the United States;
- (ii) Designed or used for collecting or conveying storm water;
- (iii) Which is not a combined sewer; and
- (iv) Which is not part of a Publicly Owned Treatment Works.”

MS4s may discharge nutrients and other pollutants to waterbodies in response to storm events. In 1990, USEPA developed rules establishing Phase I of the NPDES stormwater program, designed to prevent harmful pollutants from being washed by stormwater runoff into MS4s (or from being dumped directly into the MS4) and then discharged from the MS4 into local waterbodies. Phase I of the program required operators of “medium” and “large” MS4s (those generally serving populations of 100,000 or greater) to implement a stormwater management

program as a means to control polluted discharges from MS4s. Approved stormwater management programs for medium and large MS4s are required to address a variety of water quality related issues including roadway runoff management, municipal owned operations, hazardous waste treatment, etc.

Phase II of the rule extends coverage of the NPDES stormwater program to certain “small” MS4s. Small MS4s are defined as any MS4 that is not a medium or large MS4 covered by Phase I of the NPDES stormwater program. Only a select subset of small MS4s, referred to as “regulated small MS4s”, requires an NPDES stormwater permit. Regulated small MS4s are defined as all small MS4s located in “urbanized areas” as defined by the Bureau of the Census, and those small MS4s located outside of “urbanized areas” that are designated by NPDES permitting authorities.

In October 2000, USEPA authorized FDEP to implement the NPDES stormwater program in all areas of Florida except Indian tribal lands. FDEP’s authority to administer the NPDES program is set forth in Section 403.0885, Florida Statutes (FS). The three major components of NPDES stormwater regulations are:

- MS4 permits that are issued to entities that own and operate master stormwater systems, primarily local governments. Permittees are required to implement comprehensive stormwater management programs designed to reduce the discharge of pollutants from the MS4 to the maximum extent practicable.
- Stormwater associated with industrial activities, which is regulated primarily by a multisector general permit that covers various types of industrial facilities. Regulated industrial facilities must obtain NPDES stormwater permit coverage and implement appropriate pollution prevention techniques to reduce contamination of stormwater.
- Construction activity general permits for projects that ultimately disturb one or more acres of land and which require the implementation of stormwater pollution prevention plans to provide for erosion and sediment control during construction.

Stormwater discharges conveyed through the storm sewer system covered by the permit are subject to the WLA of the TMDL. Any newly designated MS4s will also be required to achieve the percent reduction allocation presented in this TMDL. There is one Phase I C MS4 associated with the impaired WBID, for Escambia County (FLS000019), which also falls under the District III Florida Department of Transportation permit.

## **6.2 Nonpoint Sources**

Nonpoint sources of pollution are diffuse sources that cannot be identified as entering a waterbody through a discrete conveyance at a single location. For nutrients, these sources include runoff of agricultural fields, golf courses, and lawns, septic tanks, and residential developments outside of MS4 areas. Nonpoint source pollution generally involves a buildup of pollutants on the land surface that wash off during rain events and as such, represent contributions from diffuse sources, rather than from a defined outlet. Potential nonpoint sources are commonly identified, and their loads estimated, based on land cover data. Most methods calculate nonpoint source loadings as the product of the water quality concentration and runoff water volume associated with certain land use practices. The mean concentration of pollutants in

the runoff from a storm event is known as the event mean concentration. Figure 3.1 provides a map of the land use, while Table 3.1 lists the land use distribution in the WBID.

The following sections are organized by land use. Each section provides a description of the land use, the typical sources of nutrient loading (if applicable), and typical total nitrogen and total phosphorus event mean concentrations.

### 6.2.1 Urban Areas

Urban areas include land uses such as residential, industrial, extractive and commercial. Land uses in this category typically have somewhat high total nitrogen event mean concentrations and average total phosphorus event mean concentrations. Nutrient loading from MS4 and non-MS4 urban areas is attributable to multiple sources including stormwater runoff, leaks and overflows from sanitary sewer systems, illicit discharges of sanitary waste, runoff from improper disposal of waste materials, leaking septic systems, and domestic animals.

In 1982, Florida became the first state in the country to implement statewide regulations to address the issue of nonpoint source pollution by requiring new development and redevelopment to treat stormwater before it is discharged. The Stormwater Rule, as outlined in Chapter 403 FS, was established as a technology-based program that relies upon the implementation of Best Management Practices (BMPs) that are designed to achieve a specific level of treatment (i.e., performance standards) as set forth in Chapter 62-40, FAC.

Florida's stormwater program is unique in having a performance standard for older stormwater systems that were built before the implementation of the Stormwater Rule in 1982. This rule states: "the pollutant loading from older stormwater management systems shall be reduced as needed to restore or maintain the beneficial uses of water." [FAC 62-40-.432(2)(c)]

Nonstructural and structural BMPs are an integral part of the State's stormwater programs. Nonstructural BMPs, often referred to as "source controls", are those that can be used to prevent the generation of nonpoint source pollutants or to limit their transport off-site. Typical nonstructural BMPs include public education, land use management, preservation of wetlands and floodplains, and minimization of impervious surfaces. Technology-based structural BMPs are used to mitigate the increased stormwater peak discharge rate, volume, and pollutant loadings that accompany urbanization.

Urban, residential, and commercial developments are often a significant source of non-point source nutrients and oxygen-demanding substances. From the actual drainage area, developed land use accounts for 10 percent of the total land use, 40 percent of which is classified as high-intensity development.

#### ***Onsite Sewage Treatment and Disposal Systems (Septic Tanks)***

As stated above leaking septic tanks or onsite sewage treatment and disposal systems (OSTDs) can contribute to nutrient loading in urban areas. Water from OSTDs is typically released to the ground through on-site, subsurface drain fields or boreholes that allow the water from the tank to percolate (usually into the surficial aquifers) and either transpire to the atmosphere through

surface vegetation or add to the flow of shallow ground water. When properly sited, designed, constructed, maintained, and operated, OSTDs are a safe means of disposing of domestic waste. The effluent from a well-functioning OSTD receives natural biological treatment in the soil and is comparable to secondarily treated wastewater from a sewage treatment plant. When not functioning properly, OSTDs can be a source of nutrients, pathogens, and other pollutants to both ground water and surface water.

The State of Florida Department of Health publishes data on new septic tank installations and the number of septic tank repair permits issued for each county in Florida. Table 6.1 summarizes the cumulative number of septic systems installed in Santa Rosa County since the 1970 census and the total number of repair permits issued for the ten years between 1999-2000 and 2009-2010 (FDOH 2009). The data do not reflect septic tanks removed from service. Leaking septic systems could be a relevant source of organic and nutrient loading in the watershed.

Table 6.1 County estimates of Septic Tanks and Repair Permits.

County	Number of Septic Tanks (1970-2008)	Number of Repair Permits Issued (2000-2010)
Santa Rosa	44,171	5,709

Note: Source: <http://www.doh.state.fl.us/environment/ostds/statistics/ostdsstatistics.htm>

### 6.2.2 Pastures

Pastures include cropland and improved and unimproved pasturelands, such as non-tilled grasses woodland pastures, feeding operations, nurseries and vineyards; as well as specialty farms. Agricultural activities, including runoff of fertilizers or animal wastes from pasture and cropland and direct animal access to streams, can generate nutrient loading to streams. The highest total nitrogen and total phosphorus event mean concentrations are associated with agricultural land uses. Pastures account for 16 percent of the total land use contributed to WBID 291 from contributing subwatersheds.

### 6.2.3 Clear cut/Sparse

The clear cut/sparse land use classification includes recent clear cuts, areas of sparse vegetation or herbaceous dry prairie, shrub and brushland, other early successional areas, and mixed rangeland. Event mean concentrations for clear cut/sparse are about average for total nitrogen and low for total phosphorus. Clear cut/sparse accounts for 9 percent of the total land use from contributing subwatersheds.

### 6.2.4 Forests

Upland forests include flatwoods, oak, various types of hardwoods, conifers and tree plantations. Wildlife, located within forested areas, deposit their feces onto land surfaces where it can be transported to nearby streams during storm events. Generally, the pollutant load from wildlife is assumed to represent background concentrations. Event mean concentrations for upland forests

are low for both total nitrogen and total phosphorus. Combined forested land use accounts for the greatest amount of land use contributed to WBID 291 at 35 percent.

### **6.2.5 Water and Wetlands**

Water and Wetlands often have very low nutrient loadings, although decaying organic matter in wetlands can contribute to high organic nutrient concentrations. Open water accounts for less than 1 percent of total land use from contributing subwatersheds, while both forested and non-forested wetlands combined accounts for 14 percent of total land use. Most of the wetland land uses are located within the riparian area of Jacks Branch Creek.

### **6.2.6 Quarries/Strip mines**

Land use classification includes quarries, strip mines, exposed rock and soil, fill areas, reclaimed lands, and holding ponds. Event mean concentrations for some barren lands tend to be higher in total nitrogen. Less than one percent of total land use is made up of quarries/strip mines from contributing subwatersheds, accounting for 52 acres.

## **7.0 ANALYTICAL APPROACH**

In the development of a TMDL there needs to be a method for relating current loadings to the observed water quality problem. This relationship could be: statistical (regression for a cause and effect relationship), empirical (based on observations not necessarily from the waterbody in question) or mechanistic (physically and/or stochastically based) that inherently relate cause and effect using physical and biological relationships.

A mechanistic model was used in the development of the Jacks Branch Creek TMDL to relate the physical and biological relationships. A dynamic watershed model was used to predict the quantity of water and pollutants associated with runoff from rain events.

The period of simulation that was considered in the development of this TMDL is January 1, 2002 to December 31, 2009. The models were used to predict time series for BOD, TN, TP, and DO. The models were calibrated to current conditions and were then used to predict improvements in water quality as function of reductions in loadings.

### **7.1 Mechanistic Model**

The Loading Simulation Program in C++ (LSPC), is a watershed modeling system that includes streamlined Hydrologic Simulation Program Fortran (HSPF) algorithms for simulating hydrology, sediment, and general water quality overland as well as a simplified stream fate and transport model. LSPC is derived from the Mining Data Analysis System (MDAS), which was originally developed by USEPA Region 3 (under contract with Tetra Tech) and has been widely used for TMDLs. In 2003, the USEPA Region 4 contracted with Tetra Tech to refine, streamline, and produce user documentation for the model for public distribution. LSPC was developed to serve as the primary watershed model for the USEPA TMDL Modeling Toolbox. LSPC was used to simulate runoff (flow, biological oxygen demand, total nitrogen, total phosphorus and

dissolved oxygen) from the land surface using a daily timestep for current and natural conditions. LSPC provided tributary flows and temperature to the EFDC estuary models and tributary water quality concentrations to WASP7 estuary models.

An LSPC model was utilized to estimate the nutrient loads within and discharge from Jacks Branch Creek watershed. The LSPC model utilized the data inputs, including land use and weather data, from the larger Perdido Watershed model (USEPA 2012a and USEPA 2012b).

In order to evaluate the contributing sources to a waterbody and to represent the spatial variability of these sources within the watershed model, the contributing drainage area was represented by a series of sub-watersheds for each of the models. The sub-watersheds for the Perdido Watershed model were developed using the 12-digit hydrologic unit code (HUC12) watershed data layer and the Geological Survey (USGS) National Hydrograph Dataset (NHD). The sub-watersheds were re-delineated at a smaller scale for the Jacks Branch Creek Watershed model, once again using the NHD catchments as well as the USGS National Elevation Dataset Digital Elevation Model (Figure 7.1).




Figure 7.1 Location of Jacks Branch Creek LSPC subwatersheds

The LSPC model has a representative reach defined for each sub-watershed, and the main channel stem within each sub-watershed was used as the representative reach. The characteristics for each reach include the length and slope of the reach, the channel geometry and

the connectivity between the sub-watersheds. Length and slope data for each reach was obtained using the USGS DEM and NHD data.

The attributes supplied for each reach were used to develop a function table (FTABLE) that describes the hydrology of the stream reach by defining the functional relationship between water depth, surface area, water volume, and outflow in the segment. The assumption of a fixed depth, area, volume, outflow relationship rules out cases where the flow reverses direction or where one reach influences another upstream of it in a time-dependent way. LSPC does not model the tidal flow in the low-lying estuaries, and therefore the main Perdido Watershed model was calibrated to non-tidally influenced USGS gages.

The watershed model uses land use data as the basis for representing hydrology and nonpoint source loadings. The FDEP Level III Florida Land Use, specifically the Northwest Florida Water Management District (NFWFMD) 2004 dataset, was used to determine the land use representation. The National Landuse Coverage Dataset (NLCD) was used to develop the impervious land use representations.

The NFWFMD coverage utilized a variety of land use classes which were grouped and reclassified into 18 land use categories: beaches/dune/mud, open water, utility swaths, developed open space, developed low intensity, developed medium intensity, developed high intensity, clear-cut/sparse, quarries/strip mines, deciduous forest, evergreen forest, mixed forest, golf courses, pasture, row crop, forested wetland, non-forested wetland (salt/brackish), and non-forested wetland (freshwater). The LSPC model requires division of land uses in each sub-watershed into separate pervious and impervious land units. The NLCD 2006 percent impervious coverage was used to determine the percent impervious area associated with each land use category. Any impervious areas associated with utility swaths, developed open space, and developed low intensity, were grouped together and placed into a new land use category named *low intensity development impervious*. Impervious areas associated with medium intensity development and high intensity development were kept separate and placed into two new categories for *medium intensity development impervious* and *high intensity development impervious*, respectively. Finally, any impervious area not already accounted for in the three developed impervious categories, were grouped together into a fourth new category for all remaining impervious land use.

Soil data for the Florida watersheds was obtained from the Soil Survey Geographic Database (SSURGO). The database was produced and distributed by the Natural Resources Conservation Service (NRCS) - National Cartography and Geospatial Center (NCGC). The SSURGO data was used to determine the total area that each hydrologic soil group covered within each sub-watershed. The sub-watersheds were represented by the hydrologic soil group that had the highest percentage of coverage within the boundaries of the sub-watershed. There were four hydrologic soil groups which varied in their infiltrations rates and water storage capacity.

In the watershed models, nonpoint source loadings and hydrological conditions are dependent on weather conditions. Hourly data from weather stations within the boundaries of, or in close proximity to, the sub-watersheds were applied to the watershed model. A weather data forcing file was generated in ASCII format (\*.air) for each meteorological station used in the hydrological evaluations in LSPC. Each meteorological station file contained atmospheric data

used in modeling the hydrological processes. These data included precipitation, air temperature, dew point temperature, wind speed, cloud cover, evaporation, and solar radiation. These data are used directly, or calculated from the observed data. The Perdido Watershed model weather stations contained data from 1996 through 2009.

The hydrodynamic calibration parameters from the larger Perdido Watershed model were used to populate the Jacks Branch Creek watershed model. The Perdido Watershed model was calibrated to continuous flow USGS gages. No continuous measured flow data was located in the Jacks Branch Creek watershed, so no calibration updates were done for flow in Jacks Branch Creek and the Perdido Watershed model parameterization was used.

Water quality parameters from the larger Perdido Watershed model were used to populate the Jacks Branch Creek Watershed model. The Perdido Watershed model was calibrated to several water quality stations whose data was taken from IWR38. The Jacks Branch Creek watershed was calibrated to water quality data from IWR44, specifically to station 21FLPNS 33010130, 21FLBRA 291-A, 21FLGW 34818, and 21FLGW 35227, all of which contained data records for the parameters of interest. LSPC water quality calibration results are presented in Figure 7.2 to Figure 7.13 in the Current Condition scenario, Section 7.2.1.

## **7.2 Scenarios**

Two modeling scenarios were developed and evaluated in this TMDL determination: a current condition and a natural condition scenario. Concentrations and loadings were evaluated to determine if DO concentrations in the natural condition scenario could meet the DO standard, and the impact of nutrients on the DO concentrations. The results from the scenarios were used to develop the TMDL.

### **7.2.1 Current Condition**

The current condition scenario evaluated current hydrologic and water quality conditions in the watershed, specifically water quality concentration and loadings at the outlet of WBID 291. The current condition annual average concentrations for Jacks Branch Creek are presented in Table 7.1. The current condition simulation was used to determine the base loadings for the WBID. The base loading (7.2), when compared with the TMDL scenarios, were used to determine the percent reduction in nutrient loads that will be needed to achieve water quality standards. Figure 7.2 through Figure 7.13 provide calibrated current condition modeled parameters for the Jacks Branch Creek watershed.




Figure 7.2 Modeled vs. Observed Temperature (°C) at 21FLPNS 33010130 and 21FLBRA 291-A




Figure 7.3 Modeled vs. Observed Temperature (°C) at 21FLGW 34818 and 21FLGW 35227




Figure 7.4 Modeled vs. Observed DO (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A




Figure 7.5 Modeled vs. Observed DO (mg/l) at 21FLGW 34818 and 21FLGW 35227




Figure 7.6 Modeled vs. Observed BOD<sub>5</sub> (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A




Figure 7.7 Modeled vs. Observed BOD<sub>5</sub> (mg/l) at 21FLGW 34818 and 21FLGW 35227




Figure 7.8 Modeled vs. Observed Total Nitrogen (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A




Figure 7.9 Modeled vs. Observed Total Nitrogen (mg/l) at 21FLGW 34818 and 21FLGW 35227




Figure 7.10 Modeled vs. Observed Total Phosphorus (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A




Figure 7.11 Modeled vs. Observed Total Phosphorus (mg/l) at 21FLGW 34818 and 21FLGW 35227




Figure 7.12 Modeled vs. Observed Chlorophyll a (ug/L) at 21FLPNS 33010130 and 21FLBRA 291-A




Figure 7.13 Modeled vs. Observed Chlorophyll a (ug/L) at 21FLGW 34818 and 21FLGW 35227

Table 7.1 Current condition concentrations in the impaired WBID in the Perdido River basin.

Parameter	WBID 291
Total nitrogen (mg/L)	0.56
Total phosphorus (mg/L)	0.01
BOD (mg/L)	1.39
DO (mg/L)	6.56

Table 7.2 Current condition loadings in the impaired WBID in the Perdido River basin.

Parameter	WBID 291	
	WLA (kg/yr)	LA (kg/yr)
Total nitrogen (mg/L)	--	25,000
Total phosphorus (mg/L)	--	488
BOD (mg/L)	--	69,408

### 7.2.2 Natural Condition

The natural condition scenario was developed to estimate water quality conditions if there was no impact from anthropogenic sources. The point sources located in the model were removed for the natural condition analysis. Land uses that were associated with anthropogenic activities (urban, agriculture, transportation, barren lands and rangeland) were converted to upland forests or forested wetlands based on the current ration of forest and wetland land uses in the model. The natural condition water quality predictions are presented in Table 7.3 and Table 7.4.

The purpose of the natural conditions scenario was to determine whether water quality standards could be achieved without abating the naturally occurring loads from the watershed. The natural condition modeling scenario indicated that the DO standard of 5 mg/L is achievable under natural conditions, indicating reducing nutrients in Jacks Branch Creek can increase DO concentrations. Figure 7.14 to Figure 7.25 provide the natural condition scenario output parameters for the Jacks Branch Creek model.




Figure 7.14 Modeled Natural Condition Temperature (°C) at 21FLPNS 33010130 and 21FLBRA 291-A




Figure 7.15 Modeled Natural Condition Temperature (°C) at 21FLGW 34818 and 21FLGW 35227




Figure 7.16 Modeled Natural Condition DO (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A




Figure 7.17 Modeled Natural Condition DO (mg/l) at 21FLGW 34818 and 21FLGW 35227




Figure 7.18 Modeled Natural Condition BOD<sub>5</sub> (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A




Figure 7.19 Modeled Natural Condition BOD<sub>5</sub> (mg/l) at 21FLGW 34818 and 21FLGW 35227




Figure 7.20 Modeled Natural Condition Total Nitrogen (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A




Figure 7.21 Modeled Natural Condition Total Nitrogen (mg/l) at 21FLGW 34818 and 21FLGW 35227




Figure 7.22 Modeled Natural Condition Total Phosphorus (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A




Figure 7.23 Modeled Natural Condition Total Phosphorus (mg/l) at 21FLGW 34818 and 21FLGW 35227

US EPA ARCHIVE DOCUMENT




Figure 7.24 Modeled Natural Condition Chlorophyll a (ug/L) at 21FLPNS 33010130 and 21FLBRA 291-A




Figure 7.25 Modeled Natural Condition Chlorophyll a (ug/L) at 21FLGW 34818 and 21FLGW 35227

Table 7.3 Natural condition concentrations in the impaired WBID in the Perdido River basin.

Parameter	WBID 291
Total nitrogen (mg/L)	0.20
Total phosphorus (mg/L)	0.002
BOD (mg/L)	1.03
DO (mg/L)	6.58

Table 7.4 Natural condition loadings in the impaired WBID in the Perdido River basin.

Parameter	WBID 291	
	WLA (kg/yr)	LA (kg/yr)
Total nitrogen (mg/L)	--	7,784
Total phosphorus (mg/L)	--	152
BOD (mg/L)	--	36,370

### 7.2.3 Reduction Scenario

The natural condition scenario indicated that DO standards can be achieved in Jacks Branch Creek. A scenario was developed to determine what reductions in nutrients allowed for DO to be greater than 5 mg/L throughout the modeling period. A reduction in nutrients and biochemical oxygen demand of 52 percent from anthropogenic land uses raised DO concentrations above 5 mg/L at all times. The lowest modeled DO concentration at this reduction level was 5.02 mg/L. Figure 7.26 to Figure 7.37 show the results of the scenario reduction, while Table 7.5 and Table 7.6 provide averages and loads of water quality parameters in the scenario condition. In addition, Figure 7.38 provides the cumulative distribution function of DO concentrations for both the modeled existing condition and reduction scenario results for Jacks Branch Creek. There is an increase in DO concentrations in the reduction scenario, specifically in concentrations less than 5 mg/L. In the reduction scenario, there are no modeled DO concentrations less than 5 mg/L.




Figure 7.26 Temperature (°C) at 21FLPNS 33010130 and 21FLBRA 291-A in Nutrient Reduction Scenario




Figure 7.27 Temperature (°C) at 21FLGW 34818 and 21FLGW 35227 in Nutrient Reduction Scenario




Figure 7.28 DO (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A in Nutrient Reduction Scenario




Figure 7.29 DO (mg/l) at 21FLGW 34818 and 21FLGW 35227 in Nutrient Reduction Scenario




Figure 7.30 BOD<sub>5</sub> (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A in Nutrient Reduction Scenario




Figure 7.31 BOD<sub>5</sub> (mg/l) at 21FLGW 34818 and 21FLGW 35227 in Nutrient Reduction Scenario




Figure 7.32 Observed Total Nitrogen (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A in Nutrient Reduction Scenario




Figure 7.33 Total Nitrogen (mg/l) at 21FLGW 34818 and 21FLGW 35227 in Nutrient Reduction Scenario




Figure 7.34 Observed Total Phosphorus (mg/l) at 21FLPNS 33010130 and 21FLBRA 291-A in Nutrient Reduction Scenario




Figure 7.35 Total Phosphorus (mg/l) at 21FLGW 34818 and 21FLGW 35227 in Nutrient Reduction Scenario




Figure 7.36 Chlorophyll a (ug/L) at 21FLPNS 33010130 and 21FLBRA 291-A in Nutrient Reduction Scenario




Figure 7.37 Chlorophyll a (ug/L) at 21FLGW 34818 and 21FLGW 35227 in Nutrient Reduction Scenario

Table 7.5 Reduction scenario concentrations in the impaired WBID in the Perdido River basin.

Parameter	WBID 291
Total nitrogen (mg/L)	0.32
Total phosphorus (mg/L)	0.01
BOD (mg/L)	1.16
DO (mg/L)	6.57

Table 7.6 Reduction scenario loadings in the impaired WBID in the Perdido River basin.

Parameter	WBID 291	
	WLA (kg/yr)	LA (kg/yr)
Total nitrogen (mg/L)	--	14,090
Total phosphorus (mg/L)	--	285
BOD (mg/L)	--	49,005




Figure 7.38 Dissolved Oxygen Concentration Cumulative Distribution Function

## 8.0 TMDL DETERMINATION

The TMDL for a given pollutant and waterbody is comprised of the sum of individual wasteload allocations (WLAs) for point sources, and load allocations (LAs) for both nonpoint sources and

natural background levels. In addition, the TMDL must include a margin of safety (MOS), either implicitly or explicitly, to account for the uncertainty in the relationship between pollutant loads and the quality of the receiving waterbody. Conceptually, this definition is represented by the equation:

$$\text{TMDL} = \sum \square \text{WLAs} + \sum \square \text{LAs} + \text{MOS}$$

The TMDL is the total amount of pollutant that can be assimilated by the receiving waterbody and still achieve water quality standards and the waterbody's designated use. In this TMDL development, allowable concentrations from all pollutant sources that cumulatively amount to no more than the TMDL must be set and thereby provide the basis to establish water quality-based controls. These TMDLs are expressed as annual geometric mean concentrations, since the approach used to determine the TMDL targets relied on geometric means. The TMDLs targets were determined to be the conditions needed to restore and maintain a balanced aquatic system. Furthermore, it is important to consider nutrient loading over time, since nutrients can accumulate in waterbodies.

The TMDL was determined for the concentrations and loadings at the outlet of WBID 291 and included all loadings from upstream sources and streams. During the development of this TMDL, it was determined that the natural condition scenario (all anthropogenic sources and landuses present) met the Florida standards for DO. A reduction scenario was run to determine what reduction in nutrient and BOD loads would prevent DO from violating the water quality standard. A 52 percent reduction of nutrients and BOD from anthropogenic land uses was required for DO to consistently be above the standards for the time period modeled. The averaging loading values from the scenario were then used to determine the TMDL. The allocation for WBID 291 for total nitrogen, total phosphorus, and biochemical oxygen demand is presented in Table 8.1.

Table 8.1 TMDL Load Allocations for WBID 291 in the Jacks Branch Creek Basin.

Constituent	Current Condition		TMDL Condition		Percent Reduction	
	WLA (kg/yr)	LA (kg/yr)	WLA (kg/yr)	LA (kg/yr)	LA	MS4
Total Nitrogen	NA	25,000	NA	14,090	44%	44%
Total Phosphorus	NA	488	NA	285	42%	42%
Biochemical Oxygen Demand	NA	69,408	NA	49,005	29%	29%

### **8.1 Critical Conditions and Seasonal Variation**

EPA regulations at 40 CFR 130.7(c)(1) require TMDLs to take into account critical conditions for stream flow, loading, and water quality parameters. The critical condition is the combination of environmental factors creating the "worst case" scenario of water quality conditions in the waterbody. By achieving the water quality standards at critical conditions, it is expected that water quality standards should be achieved during all other times. Seasonal variation must also be considered to ensure that water quality standards will be met during all seasons of the year, and that the TMDLs account for any seasonal change in flow or pollutant discharges, and any applicable water quality criteria or designated uses (such as swimming) that are expressed on a seasonal basis.

The critical condition for nonpoint source concentration and wet weather point source concentrations is typically an extended dry period followed by a rainfall runoff event. During the dry weather period, nutrients build up on the land surface, and are washed off by rainfall. The critical condition for continuous point source concentrations typically occurs during periods of low stream flow when dilution is minimized. Although loading of nonpoint source pollutants contributing to a nutrient impairment may occur during a runoff event, the expression of that nutrient impairment is more likely to occur during warmer months, and at times when the waterbody is poorly flushed.

### **8.2 Margin of Safety**

The Margin of Safety accounts for uncertainty in the relationship between a pollutant load and the resultant condition of the waterbody. There are two methods for incorporating an MOS into TMDLs (USEPA 1991):

- Implicitly incorporate the MOS using conservative model assumptions to develop allocations
- Explicitly specify a portion of the total TMDL as the MOS and use the remainder for Allocations

This TMDL uses an implicit MOS since the TMDL targets for nutrients were set to natural background conditions.

### **8.3 Waste Load Allocations**

Only MS4s and NPDES facilities discharging directly into lake segments (or upstream tributaries of those segments) are assigned a WLA. The WLAs, if applicable, are expressed separately for continuous discharge facilities (e.g., WWTPs) and MS4 areas, as the former discharges during all weather conditions whereas the later discharges in response to storm events.

### 8.3.1 Wastewater/Industrial Permitted Facilities

A TMDL wasteload allocation (WLA) is given to wastewater and industrial NPDES-permitted facilities discharging to surface waters within an impaired watershed. There are no continuous discharge NPDES-permitted point sources in WBID 291, therefore no WLA was calculated.

### 8.3.2 Municipal Separate Storm Sewer System Permits

The WLA for MS4s are expressed in terms of percent reductions equivalent to the reductions required for nonpoint sources. Given the available data, it is not possible to estimate concentrations coming exclusively from the MS4 areas. Although the aggregate concentration allocations for stormwater discharges are expressed in numeric form, i.e., percent reduction, based on the information available today, it is infeasible to calculate numeric WLAs for individual stormwater outfalls because discharges from these sources can be highly intermittent, are usually characterized by very high flows occurring over relatively short time intervals, and carry a variety of pollutants whose nature and extent varies according to geography and local land use. For example, municipal sources such as those covered by this TMDL often include numerous individual outfalls spread over large areas. Water quality impacts, in turn, also depend on a wide range of factors, including the magnitude and duration of rainfall events, the time period between events, soil conditions, fraction of land that is impervious to rainfall, other land use activities, and the ratio of stormwater discharge to receiving water flow.

This TMDL assumes for the reasons stated above that it is infeasible to calculate numeric water quality-based effluent limitations for stormwater discharges. Therefore, in the absence of information presented to the permitting authority showing otherwise, this TMDL assumes that water quality-based effluent limitations for stormwater sources of nutrients derived from this TMDL can be expressed in narrative form (e.g., as best management practices), provided that: (1) the permitting authority explains in the permit fact sheet the reasons it expects the chosen BMPs to achieve the aggregate wasteload allocation for these stormwater discharges; and (2) the state will perform ambient water quality monitoring for nutrients for the purpose of determining whether the BMPs in fact are achieving such aggregate wasteload allocation.

All Phase 1 MS4 permits issued in Florida include a re-opener clause allowing permit revisions for implementing TMDLs once they are formally adopted by rule. Florida may designate an area as a regulated Phase II MS4 in accordance with Rule 62-620.800, FAC. Florida's Phase II MS4 Generic Permit has a "self-implementing" provision that requires MS4 permittees to update their stormwater management program as needed to meet their TMDL allocations once those TMDLs are adopted. Permitted MS4s will be responsible for reducing only the loads associated with stormwater outfalls which it owns, manages, or otherwise has responsible control. MS4s are not responsible for reducing other nonpoint source loads within its jurisdiction. All future MS4s permitted in the area are automatically prescribed a WLA equivalent to the percent reduction assigned to the LA. The MS4 service area described in Section 6.1.2 of this report, Permit FLS000019, is required to meet the percent reduction prescribed in Table 8.1 through the implementation of BMPs.

## 8.4 Load Allocations

The load allocation for nonpoint sources was assigned a percent reduction in nutrient concentrations from the current concentrations coming into the WBID addressed in the TMDL report.

## 9.0 RECOMMENDATIONS/IMPLEMENTATION

The initial step in implementing a TMDL is to more specifically locate pollutant source(s) in the watershed. FDEP employs the Basin Management Action Plan (B-MAP) as the mechanism for developing strategies to accomplish the specified load reductions. Components of a B-MAP are:

- Allocations among stakeholders
- Listing of specific activities to achieve reductions
- Project initiation and completion timeliness
- Identification of funding opportunities
- Agreements
- Local ordinances
- Local water quality standards and permits
- Follow-up monitoring

## 10.0 REFERENCES

Florida Administrative Code. Chapter 62-40, Water Resource Implementation Rule.

Florida Administrative Code. Chapter 62-302, Surface Water Quality Standards.

Florida Administrative Code. Chapter 62-303, Identification of Impaired Surface Waters.

Florida Department of Environmental Protection (FDEP). No date. *Learn About Your Watershed: Perdido River and Bay Watershed*. <<http://www.protectingourwater.org/watersheds/map/perdido/>>. Accessed May 2012.

Florida Department of Environmental Protection (FDEP). 2006. *Water Quality Status Report*. Florida Department of Environmental Protection. <<http://waterwebprod.dep.state.fl.us/basin411/perdido/status/Perdido.pdf>>. Accessed May 2012.

Florida Department of Health (FDOH), 2009, Onsite Sewage Treatment and Disposal Systems Statistical Data, Bureau of Onsite Sewage Programs. <http://www.doh.state.fl.us/environment/ostds/statistics/ostdsstatistics.htm>

National Oceanic and Atmospheric Administration (NOAA). 2004. *Climatology of the United States: Pensacola*. National Weather Service, National Oceanic and Atmospheric

Administration. <<http://cdo.ncdc.noaa.gov/climatenormals/clim20/fl/086997.pdf>>. Accessed March, 2012.

Northwest Florida Water Management District (NFWFMD). 2004. *30-year Normal Rainfall Totals*. Northwest Florida Water Management District. <<http://www.nfwfmd.state.fl.us/rmd/rain/miscrain.htm>>. Accessed March, 2012.

Northwest Florida Water Management District (NFWFMD). 2012. *DRAFT: Surface Water Improvement and Management Plan for the Perdido River and Bay Watershed*. Northwest Florida Water Management District. <[http://www.nfwfmd.state.fl.us/pubs/Perdido/Draft\\_Perdido\\_SWIM\\_plan4-2-2012.pdf](http://www.nfwfmd.state.fl.us/pubs/Perdido/Draft_Perdido_SWIM_plan4-2-2012.pdf)>. Accessed June 2012.

United States Environmental Protection Agency (USEPA). 1991. *Guidance for Water Quality – Based Decisions: The TMDL Process*. U.S. Environmental Protection Agency, Office of Water, Washington, D.C. EPA-440/4-91-001, April 1991.

United States Environmental Protection Agency (USEPA). 2012a. *Watershed Hydrology and Water Quality Modeling Report for 19 Florida Watersheds*. U.S. Environmental Protection Agency, Office of Water, Atlanta, GA. July 2012.

United States Environmental Protection Agency (USEPA). 2012b. *Watershed Hydrology and Water Quality Modeling Report for 19 Florida Watersheds; Attachment 19: The Indian River Watershed*. U.S. Environmental Protection Agency, Office of Water, Atlanta, GA. November 2012.